

TUMKUR DIVISION.

Notification dated 10th December 1932.

1. Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division up to 3 P.M. on 10th January 1933, for Construction of a Rural Dispensary Building at Urudagere in Tumkur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed before the end of December 1933.

2. The plans, detailed estimates and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed both in words and figures.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or currency note as earnest money and be superscribed "Tender for Construction of a Rural Dispensary Building" at Urudagere, Tumkur Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, Tumkur Division who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender to the successful competitor will be required to execute the usual bond in default of which his tender will be cancelled and earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after acceptance of tenders.

11. The contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes about rates and measurements, quality of work, etc., and in all disputes of any kind the decision of the Executive Engineer will be final and legally binding on the contractor.

12. Rates should be quoted both in words and figures for each item of work and lumpsum provisions are subject to modification as per data worked out during the execution. For individual items of work under lumpsum provisions, the rates tendered for similar items of work will be paid and for other items the rates as per schedule of rates will be paid at the discretion of the Executive Engineer.

Abstract estimate for Construction of a Rural Dispensary Building at Urudagere in Tumkur Taluk.—

Serial No.	Details	Unit	Quantity as per estimate	Rate	
				In figures	In words
	<i>Dispensary.</i>				
1	Earthwork excavating foundation and filling it basement.	Cyds.	59		
2	Stone jelly concrete in mortar ...	Cft.	265		
3	Burnt size stone or trap in mud filling foundations.	"	1,134		
4	Do hammer dressed with bond stones.	"	960		
5	Burnt brick in clay ...	"	1,502		
6	Do chunam ...	"	594		
7	Teak wood doors pannelled with silicate painting and fittings complete.	Sft.	213		
8	Do battened ...	"	18		
9	Teak wood windows pannelled with $\frac{3}{4}$ " iron bars silicate painting and fittings complete.	"	116		
10	Do battened ...	"	5		

Serial No.	Items of work	Unit	Quantity as per estimate	Rate	
				In figures	In words
					Rs.
11	Burnt stone slabs 6" thick dressed and fixed.	Sft.	387		
12	Burnt stone slabs 9" thick dressed and fixed.	"	15		
13	Roofing with 1st class Mangalore tiles on teak reepers complete.	Sqr.	11.47		
14	Ridge tiles set in mortar and cement pointed.	Rft.	112		
15	Cut stone pillars with 7" sqr. with base and capital.	Each.	8		
16	Teak wood wrought and put up with wood oiling.	Cft.	89.84		
17	Chunam plastering.	Sqr.	46.55		
18	Flooring with 1½" to 2" thick cuddapah slabs on 3" concrete and cement pointing.	"	6.04		
19	Cement pointing to Basement	"	3.57		
20	Teak wood eave board (9" x 1") plain around the roof.	Rft.	197		
21	Chunam borders over roof	"	87		
22	Binding walls over roof	"	22		
23	Pukka terrace 9" thick complete	Sqr.	1.58		
24	Cornice 9" thick	Rft.	48		
25	Valley planks 1" thick with zinc sheets including mortar and cement borders.	Sft.	80		
26	Teak wood ½" planked screen with painting including groove work and door way at end.	"	56		
27	Providing sinks in dressing and compounding rooms.	L.S.	L.S.		
28	Constructing drains to lead off water	"	"		
29	Providing and fixing teak wood pegs and planks complete with wood oiling for store ward and compounding rooms.	"	"		
30	Teak wood finials 2½' long	Each.	2		
31	Do pendants 1½' long	"	12		
32	Chunam mortar moulding in front as per elevation.	L.S.	L.S.		
33	Providing rain water spouts	Each.	4		
34	White washing 2 coats	Sqr.			
35	Providing Mortar and Pestal	L.S.	L.S.		
36	Burnt brick coping with chunam plastering, and white washing complete.	Rft.	51		
37	Constructing seats in the Latrine	L.S.	L.S.		
38	Sundry unforeseen works	"	"		
39	Acquisition of the site	"	"		

A. TANDONI RAO,
Executive Engineer.